

# DAM FOUNDATION GROUTING

by  
**KEN WEAVER**



Published by the  
American Society of Civil Engineers  
345 East 47th Street  
New York, New York 10017-2398

---

**TABLE OF CONTENTS**

---

<b>PREFACE . . . . .</b>	<b>XI</b>
<b>1 INTRODUCTION . . . . .</b>	<b>1</b>
1.1 The Basics . . . . .	1
1.2 History Of Grouting In The U.S. . . . .	2
1.3 Elements Of A Successful Grout Job . . . . .	4
1.4 Limitations . . . . .	5
<b>2 DESIGN CONSIDERATIONS . . . . .</b>	<b>6</b>
2.1 General Considerations . . . . .	6
2.1.1 Predictability of Results . . . . .	6
2.1.2 Test Grouting . . . . .	7
2.1.3 Grout Curtain Depth . . . . .	8
2.1.4 Single Line vs. Multiple Line Curtains . . . . .	8
2.1.5 Grout Hole Spacing . . . . .	9
2.1.6 Blanket Grouting . . . . .	9
2.1.7 Supplementary Grouting With Chemicals . . . . .	10
2.1.8 Grout Caps . . . . .	10
2.1.9 Grout Galleries . . . . .	11
2.2 Geologic Considerations . . . . .	14
2.2.1 Primary Geologic Features . . . . .	14
2.2.2 Solution Cavities (Karst) . . . . .	15
2.2.3 Tectonic Features . . . . .	16
2.2.4 Stress Release Features and Landslides . . . . .	18
<b>3 GROUTING MATERIALS AND MIX DESIGN . . . . .</b>	<b>19</b>
3.1 Grouting Materials . . . . .	19
3.1.1 Cement . . . . .	19
3.1.1.1 Portland Cement . . . . .	19
3.1.1.2 Ultrafine Cement . . . . .	19
3.1.2 Pozzolans . . . . .	23
3.1.2.1 Fly Ash . . . . .	23
3.1.2.2 Blast Furnace Slag . . . . .	25
3.1.2.3 Condensed Silica Fume . . . . .	25
3.1.2.4 Natural Pozzolans . . . . .	26
3.1.3 Clay . . . . .	26
3.1.3.1 Bentonite . . . . .	26

3.1.3.2 Other Clay Minerals . . . . .	27
3.1.4 Fillers . . . . .	27
3.1.4.1 Sand . . . . .	27
3.1.4.2 Clay . . . . .	28
3.1.5 Chemical Additives . . . . .	28
3.1.5.1 Dispersants . . . . .	28
3.1.5.2 Accelerators . . . . .	29
3.1.5.3 Gas-Producing Agents . . . . .	29
3.1.6 Chemical Grouts . . . . .	30
3.1.7 Water . . . . .	31
3.2 Grout Mix Design . . . . .	31
3.2.1 General Considerations . . . . .	31
3.2.2 Water:Cement Ratios . . . . .	32
3.2.3 Bentonitic Grouts . . . . .	32
3.2.4 Sanded Grouts . . . . .	33
3.2.5 Fly Ash-Cement Grouts . . . . .	33
3.2.6 Clay-Cement Grouts . . . . .	34
3.3 Rheology of Grouts . . . . .	34
<b>4 FACTORS AFFECTING GROUTING EFFECTIVENESS . . . . .</b>	<b>37</b>
4.1 Material Properties Affecting Grout Penetration . . . . .	37
4.1.1 Viscosity . . . . .	37
4.1.2 Cohesion . . . . .	37
4.1.3 Specific Gravity . . . . .	38
4.1.4 Settlement (Decantation) . . . . .	38
4.1.5 Grain Size . . . . .	38
4.2 Fracture Characteristics Affecting Grout Penetration . . . . .	39
4.2.1 Fracture Aperture . . . . .	39
4.2.2 Roughness . . . . .	41
4.2.3 Hydraulic Routing . . . . .	41
4.2.4 Tortuosity . . . . .	41
4.2.5 Porosity . . . . .	42
4.2.6 Permeability . . . . .	42
4.3 Procedural Factors Affecting Grouting Effectiveness . . . . .	42
4.3.1 Orientation of Holes . . . . .	42
4.3.2 Drilling Procedures . . . . .	44
4.3.2.1 Circulating Medium . . . . .	44
4.3.2.2 Staging of Drilling . . . . .	45
4.3.2.3 Borehole Deviation . . . . .	45
4.3.3 Protection of Holes . . . . .	46
4.3.4 Grout Mixing Procedures . . . . .	47
4.3.4.1 Equipment . . . . .	47

4.3.4.2 Proportioning . . . . .	47
4.3.5 Injection Pressure . . . . .	47
4.3.6 Stage Length . . . . .	51
4.3.7 Refusal Criteria . . . . .	51
4.3.8 Closure Criteria . . . . .	53
4.4 Climatic Factors Affecting Grouting Effectiveness . . . . .	53
4.4.1 Winter Grouting . . . . .	53
4.4.2 Hot Weather Grouting . . . . .	54
4.5 Design Factors Affecting Grouting Effectiveness . . . . .	55
4.5.1 Depth of Curtain . . . . .	55
4.5.2 Width of Curtain . . . . .	56
4.5.3 Hole Spacing . . . . .	56
4.6 Influence Of Drilling Method On Grouting Effectiveness . . . . .	58
4.7 Factors Affecting Grout Durability . . . . .	58
4.7.1 Geochemical Environment . . . . .	58
4.7.1.1 Deleterious Minerals . . . . .	58
4.7.1.2 Aggressive Ground Water . . . . .	59
4.7.2 Grout Mix Design . . . . .	59
4.7.2.1 Water:Cement Ratio . . . . .	59
4.7.2.2 Grout Materials . . . . .	59
4.7.3 Hydraulic Gradient . . . . .	59
<b>5 EQUIPMENT . . . . .</b>	<b>61</b>
5.1 Drilling Equipment . . . . .	61
5.1.1 Rotary Equipment . . . . .	61
5.1.2 Percussion Equipment . . . . .	62
5.1.3 Rotary-Percussion Equipment . . . . .	65
5.2 Washing And Testing Equipment . . . . .	66
5.2.1 Washing Equipment . . . . .	66
5.2.2 Water Testing Equipment . . . . .	68
5.3 Grouting Equipment . . . . .	68
5.3.1 Mixers . . . . .	68
5.3.1.1 Colloidal Mixers . . . . .	68
5.3.1.2 Paddle Mixers . . . . .	73
5.3.1.3 Other Types . . . . .	73
5.3.2 Water Meters . . . . .	74
5.3.3 Agitators . . . . .	74
5.3.4 Pumps . . . . .	75
5.3.5 Headers . . . . .	77
5.3.6 Packers . . . . .	79
5.3.7 Sleeve Tubes . . . . .	80
5.3.8 Equipment Layout . . . . .	82

5.4 Automated Systems . . . . .	83
5.4.1 Drilling Parameter Recorders . . . . .	85
5.4.1.1 EN.PA.SOL . . . . .	85
5.4.1.2 Lutz Drilling Parameter Recorders . . . . .	85
5.4.1.3 Papero . . . . .	86
5.4.2 Grouting Parameter Recorders . . . . .	86
5.4.2.1 Craelius Recording System . . . . .	87
5.4.2.2 Häny Recording Systems . . . . .	88
5.4.2.3 Lutz Grouting Parameter Recorders . . . . .	88
5.4.2.4 Paguro System . . . . .	88
5.4.2.5 CRT Display Recorders . . . . .	90
5.4.3 Automated Headers . . . . .	90
5.4.4 Automated Batching Systems . . . . .	90
5.4.5 Automated Injection Systems . . . . .	91
5.5 Miscellaneous Equipment . . . . .	92
5.5.1 Hydration Tanks . . . . .	92
5.5.2 Winches . . . . .	92
5.5.3 Scaffolding . . . . .	92
5.5.4 Mobile Platforms . . . . .	95
5.6 Uplift Monitoring Devices . . . . .	95
5.6.1 General Considerations . . . . .	95
5.6.2 Rigid Bar Extensometers . . . . .	95
5.6.3 Alarm Extensometers . . . . .	97
5.6.4 Tiltmeters . . . . .	97
<b>6 STANDARD PROCEDURES . . . . .</b>	<b>98</b>
6.1 Pattern And Sequence . . . . .	98
6.1.1 Multiple Row Curtains . . . . .	98
6.1.2 Split-Spacing Sequence . . . . .	98
6.2 Drilling Procedures . . . . .	99
6.3 Washing Procedures . . . . .	100
6.3.1 Special Washing . . . . .	100
6.3.2 Pressure Washing . . . . .	101
6.4 Water Testing Procedures . . . . .	101
6.4.1 General Considerations . . . . .	101
6.4.2 Lugeon Tests . . . . .	103
6.4.3 Routine Tests . . . . .	104
6.4.4 Special Tests . . . . .	105
6.5 Grouting Procedures . . . . .	105
6.5.1 General Procedures . . . . .	105
6.5.1.1 Ascending Stage Grouting . . . . .	105
6.5.1.2 Descending Stage Grouting . . . . .	106

6.5.1.3 Circuit Grouting . . . . .	106
6.5.2 Agitator Calibration Procedures . . . . .	108
6.5.3 Packer Sealing Procedures . . . . .	110
6.5.4 Mixing Procedures . . . . .	110
6.5.5 Grout Injection Procedures . . . . .	111
6.5.5.1 Basic Procedures . . . . .	111
6.5.5.2 Injection Pressures . . . . .	113
6.5.5.3 Use of Grout Mix Chart . . . . .	115
6.5.5.4 Treatment of Caving Holes . . . . .	117
6.5.5.5 Grout Communication Between Holes . . . . .	117
6.5.5.6 Lost Circulation Zones . . . . .	120
6.5.5.7 Artesian Flow . . . . .	120
6.5.5.8 Treatment of Surface Leakage . . . . .	121
6.5.5.9 Leaking Packers . . . . .	121
6.5.5.10 Implementation of Refusal Criterion . . . . .	122
6.5.6 Special Problems . . . . .	123
6.5.6.1 Flowing Water . . . . .	123
6.5.6.2 Natural Gas . . . . .	123
6.5.7 Hole Backfilling . . . . .	123
6.6 Protection Of Grout Holes . . . . .	124
<b>7 SUPERVISION AND INSPECTION OF GROUTING . . . . .</b>	<b>125</b>
7.1 Preamble . . . . .	125
7.2 Supervision . . . . .	125
7.3 Inspection . . . . .	125
7.4 Duties Of Inspectors . . . . .	126
7.4.1 Record Keeping . . . . .	126
7.4.2 Inspection of Drilling Operations . . . . .	126
7.4.2.1 Grout Holes . . . . .	126
7.4.2.2 Cored Verification Holes . . . . .	127
7.4.3 Inspection of Grouting Operations . . . . .	128
7.4.3.1 Preparation for Grouting . . . . .	128
7.4.3.2 Basic Inspection Procedures . . . . .	128
7.4.3.3 Field Testing . . . . .	129
7.4.4 Safety Considerations . . . . .	129
7.5 Duties Of Data Coordinator . . . . .	130
<b>8 RECORDS . . . . .</b>	<b>131</b>
8.1 Field Records . . . . .	131
8.1.1 Drilling Logs . . . . .	131
8.1.2 Daily Drilling Reports . . . . .	133

8.1.3 Pressure Testing and Grouting Logs . . . . .	133
8.1.4 Daily Grouting Reports . . . . .	135
8.1.5 Field Testing Reports . . . . .	135
8.1.6 Progress Drawings . . . . .	135
8.2 Office Records . . . . .	135
8.2.1 Tabulations . . . . .	135
8.2.1.1 Progress Tabulations . . . . .	135
8.2.1.2 Payment Item Tabulations . . . . .	135
8.2.1.3 Summary of Drilling and Grouting Data . . . . .	135
8.2.2 Progress Charts . . . . .	135
8.2.3 Plan Drawings . . . . .	140
8.2.4 Grouting Profiles . . . . .	140
<b>9 QUALITY ASSURANCE . . . . .</b>	<b>142</b>
9.1 Review Process . . . . .	142
9.2 Closure Criteria . . . . .	142
9.2.1 Permeability Criteria . . . . .	142
9.2.2 Grout Take Criteria . . . . .	144
9.3 Statistical Evaluation Procedures . . . . .	145
9.3.1 Reduction Ratios . . . . .	145
9.3.2 Mean Value Bar Graphs . . . . .	147
9.3.3 Frequency Distribution Histograms . . . . .	147
9.3.4 Summation Curves . . . . .	148
9.3.5 Permeability Profiles . . . . .	148
9.4 Detailed Evaluation . . . . .	148
9.5 Laboratory Testing . . . . .	151
9.5.1 Set Time . . . . .	151
9.5.2 Cohesion . . . . .	152
9.5.3 Compatibility . . . . .	152
9.6 Field Testing . . . . .	152
9.6.1 Density Test . . . . .	153
9.6.2 Marsh Viscosity Test . . . . .	153
9.6.3 ASTM Flow Cone Test . . . . .	154
9.6.4 Bleed Test . . . . .	156
<b>10 ELEMENTS OF GOOD GROUTING PRACTICE . . . . .</b>	<b>157</b>
10.1 General Comments . . . . .	157
10.2 Geologic Considerations . . . . .	158
10.3 Other Basic Considerations . . . . .	159
10.4 Technical Specifications . . . . .	160
10.4.1 Flexibility . . . . .	161

10.4.2 Surface Treatment . . . . .	161
10.4.3 Drilling Equipment and Procedures . . . . .	161
10.4.4 Water Testing . . . . .	162
10.4.5 Grouting Equipment and Procedures . . . . .	162
10.5 Prequalification Of Bidders . . . . .	162
10.6 Project Review . . . . .	163
<b>REFERENCES . . . . .</b>	<b>165</b>
<b>INDEX . . . . .</b>	<b>175</b>

## LIST OF TABLES

---

1. MC-100 grout slurry characteristics. . . . .	23
2. Effect of bentonite on bleed. . . . .	33
3. Selected properties of typical fly ash-cement grouts. . . . .	34
4. Conversion factors. . . . .	51
5. Colloidal mixer data. . . . .	70
6. Interpretation of pressure-take trends. . . . .	112
7. Identification and mitigation of problems. . . . .	143
8. Examples of typical reduction ratios. . . . .	146

## LIST OF FIGURES

---

1. Permeation of granular materials by particulate grouts. . . . .	21
2. Grain size distribution of particulate grouts. . . . .	21
3. Pozzolanic grout filling fractures in sandstone and shale. . . . .	27
4. Graphical representation of fluid types. . . . .	35
5. Effect of fracture aperture and frequency on permeability. . . . .	40
6. Seepage channels created by groundwater flow in friable sandstone, La Vuelta Dam, Venezuela. . . . .	43
7. Injection pressures used in U.S. grouting practice. . . . .	48
8. Injection pressures used in Swedish grouting practice. . . . .	48
9. Grout plant in air-supported structure for winter grouting at Merrill Creek Project, New Jersey. . . . .	55
10. Water jacket for cooling grout circulation lines for hot weather grouting. . . . .	57
11. Typical column-mounted drill rig. . . . .	62

12. Typical track-mounted percussion drill.	63
13. Typical button bits for percussion drilling.	63
14. Special washing head used by the Water Resources Commission of New South Wales.	67
15. Typical water test setup.	68
16. Schematic diagram of Colcrete double-drum colloidal grout mixer.	69
17. Häny high-turbulence colloidal grout mixer.	69
18. Typical grout agitator, showing deflectors to induce turbulence.	71
19. Progressing cavity grout pump with automotive-type transmission.	76
20. Synchronized piston grout pumps, on skid-mounted grout plant.	76
21. Typical grout header.	78
22. Saunders valve grout header.	78
23. Typical packers for grouting operations.	80
24. Typical sleeve tubes (rubber sleeves are rolled back to show grout ports).	81
25. Schematic diagram of typical grout layout specified for use on California Dept. of Water Resources projects.	83
26. Typical skid-mounted grout plant, with progressing cavity-type grout pump.	84
27. Typical trailer-mounted grout plant.	84
28. Häny grouting data recording system.	89
29. ISE automated grout header.	91
30. Drill rig secured on steep slope by use of a winch.	93
31. Air-powered winch, anchored to regularizing concrete.	93
32. Typical scaffolding for grouting operations.	94
33. Schematic diagram of typical rigid bar extensometer	96
34. Schematic illustration of downward staying sequence.	107
35. Comparison of hypothesized conditions in borehole during conventional grouting and circuit grouting of open fissure.	109
36. Cement content of neat portland cement grout mixes.	116
37. Schematic hookup for circuit grouting.	118
38. Schematic diagram of multiple hookup.	119
39. Typical grout hole drill log.	132
40. Typical daily drilling report.	134
41. Typical pressure testing and grouting log.	136
42. Typical daily grouting report.	137
43. Typical field testing form.	138
44. Typical drilling and grouting progress drawing for field use.	139
45. Typical summary of drilling and grouting data.	141
46. Examples of frequency distribution histograms.	149
47. Grout density test using mud balance.	154
48. Marsh viscosity test.	155