

# ARTIFICIAL SAND FILLS IN WATER



A.A. BALKEMA / ROTTERDAM / BROOKFIELD / 1992

## CONTENTS

	LIST OF SYMBOLS . . . . .	14	
	ABBREVIATIONS . . . . .	17	
Chapter	1	INTRODUCTION . . . . .	19
	1.1	General. . . . .	19
	1.2	Use and objectives . . . . .	19
	1.3	Continuation . . . . .	20

## THEORY

Chapter	2	PROCESS PHENOMENA OF BUILDING WITH SAND IN WATER . . . . .	25
	2.1	Summary . . . . .	25
	2.2	Slope formation in the borrow pit. . . . .	27
	2.3	Falling of a sand-water mixture through water . . . . .	28
	2.4	Formation of craters . . . . .	30
	2.5	Flowing of a sand-water mixture above water . . . . .	32
	2.6	Flowing of a sand-water mixture under water . . . . .	35
	2.7	Loss of sand under water . . . . .	36
	2.8	Sedimentation and slope formation . . . . .	36
Chapter	3	SOIL INVESTIGATION IN THE BORROW AREA . . . . .	41
	3.1	Need for soil investigations . . . . .	41
	3.2	Review of investigation methods . . . . .	43
	3.3	Extent and phasing of investigations . . . . .	46
Chapter	4	FALLING OF A SAND-WATER MIXTURE THROUGH WATER . . . . .	47
	4.1	Hydraulic sand placing processes . . . . .	47
	4.1.1	Methods of hydraulic placing . . . . .	47
	4.1.2	Fall processes. . . . .	47
	4.1.3	Impact processes . . . . .	49
	4.2	Jet/plume mechanism . . . . .	50
Chapter	5	FORMATION OF CRATERS . . . . .	53
	5.1	Dimensions of a whirl crater . . . . .	53
	5.1.1	Erosion by clear water jets . . . . .	53
	5.1.2	Effect of sand in a water jet on the dimensions of a crater .	57
	5.1.3	Erosion by round sand-water jets; alternative approach . .	58

5.1.4	Example . . . . .	59	
5.2	Time scale of erosion processes . . . . .	60	
5.3	Mixture overflow from crater . . . . .	61	
<b>Chapter</b>	<b>6</b>	<b>SEDIMENTATION AND EROSION PROCESSES . . . . .</b>	<b>65</b>
6.1	Equilibrium flow . . . . .	65	
6.2	Sedimentation during grain flow . . . . .	65	
6.3	Sedimentation during suspension flow . . . . .	65	
6.4	Sedimentation during flow slides . . . . .	69	
6.5	Erosion . . . . .	69	
<b>Chapter</b>	<b>7</b>	<b>HYPERCONCENTRATED SAND-WATER MIXTURE FLOW ABOVE WATER . . . . .</b>	<b>71</b>
7.1	Methods of hydraulic placement . . . . .	71	
7.2	Types of sand-water mixture flow . . . . .	72	
7.3	Bed-form types on the hydraulic sand fill . . . . .	73	
7.4	Equilibrium slope . . . . .	75	
<b>Chapter</b>	<b>8</b>	<b>HYPERCONCENTRATED SAND-WATER MIXTURE FLOW UNDER WATER . . . . .</b>	<b>79</b>
8.1	Methods of hydraulic placement . . . . .	79	
8.2	Types of sand-water mixture flow . . . . .	79	
8.3	Bed-form types on the underwater hydraulic sand fill . . . . .	79	
8.4	Slope development under water of a sand fill . . . . .	80	
8.5	Sand fill slopes beneath water level . . . . .	83	
8.6	Sand losses during hydraulic sand placement . . . . .	84	
<b>Chapter</b>	<b>9</b>	<b>FLOW SLIDES . . . . .</b>	<b>87</b>
9.1	General . . . . .	87	
9.2	Explanation of the flow slide phenomenon . . . . .	88	
9.3	Practical advice for naturally settled sand . . . . .	89	
9.4	Flow slides during hydraulic placing of fill under water . . . . .	90	
9.5	Measures to prevent flow slides . . . . .	93	
9.5.1	Compaction . . . . .	93	
9.5.2	Slope regrading . . . . .	93	
9.5.3	Measures during the hydraulic placement of sand . . . . .	93	
9.5.4	Measures during the sand winning process . . . . .	94	
<b>Chapter</b>	<b>10</b>	<b>COMPACTION . . . . .</b>	<b>95</b>
10.1	Introduction . . . . .	95	
10.2	Short description of methods and applicability . . . . .	96	
10.3	Factors influencing the degree of compaction . . . . .	100	
10.4	Selection of the method and control of the results . . . . .	100	

Chapter	11	MEASUREMENT OF PROCESS PARAMETERS . . . . .	102
	11.1	Sand characteristics. . . . .	102
	11.2	Flow rate and concentration in the discharge pipe. . . . .	102
	11.2.1	Mixture flow rate. . . . .	102
	11.2.2	Concentration or mixture density. . . . .	103
	11.2.3	Sand production . . . . .	103
	11.3	Geometry of the fill area above water level . . . . .	103
	11.4	Mixture velocity on the abovewater fill area . . . . .	105
	11.5	Sand concentrations on the fill area. . . . .	106
	11.6	Measuring of sand fill densities. . . . .	108
	11.6.1	General. . . . .	108
	11.6.2	Electric density measurement. . . . .	108
	11.6.3	Nuclear density measurement. . . . .	109
	11.6.4	Density of frozen samples . . . . .	109
	11.6.5	Minimum and maximum density . . . . .	109
	11.6.6	Critical density . . . . .	110
	11.6.7	Dutch cone penetration tests . . . . .	111
Chapter	12	SPECIAL MEASUREMENTS. . . . .	112
	12.1	Measurements of flow slides . . . . .	112
	12.1.1	General. . . . .	112
	12.1.2	Echo-sounding surveys . . . . .	113
	12.1.3	Side scan sonar. . . . .	113
	12.1.4	Pore pressure meters . . . . .	113
	12.1.5	Density meters . . . . .	114
	12.1.6	„Dishes“ or „underwater floats“ . . . . .	114
Chapter	13	SUMMARY OF THE THEORY FOR PRACTICAL USE . . . . .	116
	13.1	General. . . . .	116
	13.2	Slope formation in the borrow pit. . . . .	116
	13.3	Falling of a sand-water mixture through water . . . . .	116
	13.4	Crater formation . . . . .	117
	13.5	Sedimentation on a fill area above water . . . . .	118
	13.6	Sedimentation on a fill area under water . . . . .	118

## PRACTICE

Chapter	14	EXTERNAL CONDITIONS DURING CONSTRUCTION . . . . .	123
	14.1	Subdivision into groups. . . . .	123
	14.2	Workability. . . . .	123
	14.3	Hydraulic and morphological changes. . . . .	126
	14.4	Environmental aspects . . . . .	126

Chapter	15	STRUCTURE TYPES, FUNCTIONS AND REQUIREMENTS . . . . .	129
	15.1	Review of structure types . . . . .	129
	15.2	Sand fills and covering of pipelines . . . . .	130
	15.3	Sand backfills around tunnels and large ducts submerged in pre-dredged trenches . . . . .	131
	15.4	Backfilling and embankments behind quay wall structures .	132
	15.5	Underwater embankments or trench backfill using sand . .	134
	15.6	Building up above water level of sand fills constructed in water	135
Chapter	16	EQUIPMENT AND WORK METHODS FOR THE WINNING OF SAND .	137
	16.1	Introduction . . . . .	137
	16.2	General description of the most common sand winning methods . . . . .	137
	16.2.1	Suction dredging . . . . .	137
	16.2.2	Cutter suction dredging . . . . .	138
	16.2.3	Trailing suction dredging . . . . .	139
	16.3	Composition of the sand in the winning area . . . . .	140
	16.4	Depth and thickness of the dredgeable layers . . . . .	141
	16.5	Location of the winning area in relation to waves and shipping	141
	16.6	Acceptable dredging tolerances . . . . .	142
	16.7	Presence of unsuitable overburden . . . . .	143
	16.8	Boundary of the future borrow pit . . . . .	143
Chapter	17	WORK METHODS FOR SAND FILLING . . . . .	145
	17.1	General . . . . .	145
	17.2	Positioning in place of the equipment . . . . .	145
	17.3	Workability . . . . .	147
	17.4	Draught and maximum berm height . . . . .	148
	17.5	Control of the discharge process and bridge formation . .	148
Chapter	18	QUANTITY MEASUREMENT FOR CONSTRUCTION AND PAYMENT .	152
	18.1	Purpose and location of the measurement . . . . .	152
	18.2	Inaccuracies in the measurements . . . . .	152
	18.3	Bulking of the soil . . . . .	153
	18.4	In and out survey by means of soundings . . . . .	153
	18.5	Measurement in the hopper or barge . . . . .	154
	18.6	Measurement in the discharge pipeline . . . . .	154
	18.7	Measurement on the fill area . . . . .	154
Chapter	19	QUALITY ASSURANCE AND PROCESS CONTROL . . . . .	155
	19.1	Introduction . . . . .	155
	19.2	Quality assurance in practice . . . . .	155

19.3	Formulating needs . . . . .	156	
19.4	Design . . . . .	156	
19.4.1	Design process . . . . .	156	
19.4.2	Functional requirements and data. . . . .	157	
19.4.3	Development of alternative designs and considerations . . . . .	158	
19.4.4	Final design . . . . .	158	
19.4.5	Verifications . . . . .	159	
19.4.6	Tolerances . . . . .	159	
19.5	Work preparation. . . . .	160	
19.6	Construction . . . . .	162	
19.7	Commission and verification . . . . .	164	
<b>Chapter</b>	<b>20</b>	<b>CASE HISTORIES . . . . .</b>	<b>165</b>
20.1	Drilling island Issungnak, Beaufort Sea, 1979 . . . . .	165	
20.1.1	Introduction . . . . .	165	
20.1.2	External conditions. . . . .	165	
20.1.3	Structure to be made . . . . .	165	
20.1.4	Types of equipment and work methods . . . . .	166	
20.1.5	Construction aspects . . . . .	166	
20.1.6	Feedback with theory. . . . .	166	
20.2	Drilling island Uviluk, Beaufort Sea, 1982. . . . .	167	
20.2.1	Introduction . . . . .	167	
20.2.2	External conditions. . . . .	168	
20.2.3	Structure to be made . . . . .	168	
20.2.4	Types of equipment and work methods . . . . .	168	
20.2.5	Construction aspects . . . . .	169	
20.2.6	Feedback with theory. . . . .	170	
20.3	Insulating of subsea flowlines, Nessfield and Gullfaks, North Sea, 1988. . . . .	170	
20.3.1	Introduction . . . . .	170	
20.3.2	External conditions. . . . .	171	
20.3.3	Structure to be made . . . . .	172	
20.3.4	Types of equipment and work methods . . . . .	172	
20.3.5	Construction aspects . . . . .	172	
20.4	Flushing and pipeline discharging underneath tunnel . . . . .	173	
20.4.1	Introduction . . . . .	173	
20.4.2	Brief description of applied method. . . . .	174	
20.4.3	Some practical figures . . . . .	175	
20.4.4	Preparation and trench clean-up . . . . .	175	
20.4.5	Hindrance to shipping . . . . .	175	
20.5	Construction of a ring dam in the North Sea, Rotterdam-Europoort, 1986/1987 . . . . .	176	

20.5.1	Introduction . . . . .	176
20.5.2	External conditions . . . . .	176
20.5.3	Structure to be made . . . . .	180
20.5.4	Types of equipment and work methods . . . . .	180
20.5.5	Construction aspects . . . . .	183
20.6	Construction of a steeper gradient of an existing underwater slope . . . . .	183
20.6.1	Introduction . . . . .	183
20.6.2	External conditions . . . . .	183
20.6.3	Structure to be made . . . . .	184
20.6.4	Types of equipment and work methods . . . . .	184
20.6.5	Construction aspects . . . . .	185
20.7	Backfilling of a sinker trench in the Beer Canal, Rotterdam-Europoort . . . . .	185
20.7.1	Introduction . . . . .	185
20.7.2	External conditions . . . . .	185
20.7.3	Structure to be made . . . . .	186
20.7.4	Types of equipment and work methods . . . . .	186
20.7.5	Construction aspects . . . . .	186
20.7.6	Feedback with theory . . . . .	187
20.8	Backfilling of a sinker trench in the Caland Canal, Rotterdam-Europoort . . . . .	189
20.8.1	Introduction . . . . .	189
20.8.2	External conditions . . . . .	189
20.8.3	Structure to be made . . . . .	189
20.8.4	Types of equipment and work methods . . . . .	189
20.8.5	Construction aspects . . . . .	189
20.8.6	Feedback with theory . . . . .	190
20.9	Sand placement for soil improvement under a construction dock dike, River Ems near Leer in Germany . . . . .	191
20.9.1	Introduction . . . . .	191
20.9.2	External conditions . . . . .	191
20.9.3	Structure to be made . . . . .	192
20.9.4	Types of equipment and work methods . . . . .	192
20.9.5	Construction aspects . . . . .	193
20.9.6	Feedback with theory . . . . .	194
20.10	Krammer sill, Eastern Scheldt Estuary, the Netherlands, 1987	194
20.10.1	Introduction . . . . .	194
20.10.2	External conditions . . . . .	196
20.10.3	Structure to be made . . . . .	198
20.10.4	Types of equipment and work methods . . . . .	199
20.10.5	Construction aspects . . . . .	200

20.11	Relocation of a dam, Rotterdam-Europort . . . . .	201
20.11.1	Introduction . . . . .	201
20.11.2	External conditions . . . . .	201
20.11.3	Structure to be made . . . . .	202
20.11.4	Types of equipment and work methods . . . . .	202
20.11.5	Construction aspects . . . . .	203
20.11.6	Analysis . . . . .	204
20.11.7	Recommendations . . . . .	205
20.12	Dredging and backfilling of a trench for a gas pipeline, Zuidwal project, Waddenzee, the Netherlands . . . . .	205
20.12.1	Introduction . . . . .	205
20.12.2	External conditions . . . . .	205
20.12.3	Structure to be made . . . . .	206
20.12.4	Types of equipment and work methods . . . . .	207
20.12.5	Construction aspects . . . . .	207
20.13	Construction of the superstructure of a spending beach break- water, Saldanha Bay, South Africa, 1975/1976 . . . . .	208
20.13.1	Introduction . . . . .	208
20.13.2	External conditions . . . . .	209
20.13.3	Structure to be made . . . . .	211
20.13.4	Types of equipment and work methods . . . . .	212
20.13.5	Construction aspects . . . . .	214
<b>Chapter 21</b>	<b>CASE STUDY . . . . .</b>	<b>218</b>
	Construction of an underwater dam for a construction dock for a container terminal in Rotterdam-Europort, 1988	
21.1	Problem definition and situation . . . . .	218
21.1.1	Problem definition . . . . .	218
21.1.2	Situation . . . . .	219
21.1.3	External conditions . . . . .	219
21.2	Geotechnical pre-survey . . . . .	221
21.2.1	Purpose of pre-survey . . . . .	221
21.2.2	Available grain size distributions . . . . .	221
21.2.3	Soil investigation . . . . .	222
21.2.4	Geotechnical advice based on soil investigation . . . . .	222
21.3	Method of execution . . . . .	223
21.3.1	Alternatives and final choice . . . . .	223
21.3.2	Calculations of the crater dimensions and the slope gradient	224
21.4	Contract specifications and tender procedure . . . . .	226
21.4.1	Description of contract specifications . . . . .	226
21.4.2	Tender procedure . . . . .	227
21.5	Verification measurements during hydraulic filling . . . . .	227

21.5.1	General . . . . .	227
21.5.2	Construction method . . . . .	227
21.5.3	Surveys . . . . .	228
21.5.4	Testing of sand in the supplied barges . . . . .	228
21.6	Supplementary investigation . . . . .	230
21.6.1	In situ investigation . . . . .	230
21.6.2	Laboratory investigation . . . . .	233
21.7	Evaluation . . . . .	235
21.7.1	Discussion of the investigation results . . . . .	235
21.7.2	Conclusions . . . . .	237
Chapter 22	SUMMARY . . . . .	239
Appendix A	DISCHARGE PROCESS PARAMETERS . . . . .	241
A1	Introduction . . . . .	241
A2	Density, porosity and void ratio of soil . . . . .	242
A3	Parameters in relation to the dredging process . . . . .	242
A3.1	Mixture density . . . . .	242
A3.2	Mixture flow rate and mixture velocity . . . . .	242
A3.3	Concentration . . . . .	243
A4	Parameters in relation to the behaviour of the mixture on the fill area . . . . .	245
A4.1	Specific mixture flow rate . . . . .	246
A4.2	Specific sand production . . . . .	246
A4.3	Specific sand transport . . . . .	246
A5	Parameters in relation to the change of volume of the dredged soil . . . . .	247
A5.1	Bulking and debulking . . . . .	247
Appendix B	DRILLING ISLANDS ISSUNGNAK AND UVILUK . . . . .	250
B1	General . . . . .	250
B2	Bottom discharging with split barges (Issungnak) . . . . .	250
B3	Pipeline discharging from the water surface (Issungnak) . . . . .	252
B4	Hydraulic discharging on abovewater fill area (Issungnak) . . . . .	255
B5	Hydraulic discharging just above sea bed (Uviluk) . . . . .	255
B6	Flow slides . . . . .	257
B7	Conclusions . . . . .	258
Appendix C	SAND TUBES . . . . .	259
C1	Introduction . . . . .	259
C2	Fabrication of sand tubes . . . . .	259
C3	Placing of sand tubes . . . . .	260
C4	Characteristics of sand tubes . . . . .	261
C5	Protection of sand tubes . . . . .	261

Appendix D	QUALITY ASSURANCE . . . . .	262
D1	Introduction . . . . .	262
D2	Definitions . . . . .	262
D3	What is quality assurance . . . . .	263
D4	Why is quality assurance so important . . . . .	263
D5	How can quality assurance be implemented in a company .	265
D6	Project oriented quality control . . . . .	265
D7	Reliability analysis . . . . .	267
Appendix E	REFERENCES . . . . .	268
Appendix F	KEY-WORDS . . . . .	272
Appendix G	QUESTIONNAIRE . . . . .	278