

Transportation Tunnels

S. PONNUSWAMY

Former Additional General Manager
Southern Railway, Madras

and

D. JOHNSON VICTOR

Former Professor of Civil Engineering
Indian Institute of Technology, Madras



A.A. BALKEMA/ROTTERDAM/BROOKFIELD/1996



Contents

FOREWORD	v
PREFACE	vii
1 INTRODUCTION	1
1.1 General	1
1.2 Classification	1
1.3 Transportation Tunnels	2
1.4 Subway Tunnels	3
1.5 Highway Tunnels	3
1.6 Tunnels in India	4
1.7 Scope of this Book	4
2 PRELIMINARY INVESTIGATIONS AND SURVEYS	5
2.1 Economic Analysis	5
2.2 Location	8
2.3 Alignment Geometry	8
2.4 Gradients	9
2.4.1 Rail and other Resistances	9
2.4.2 Highway Tunnels	9
2.5 Sequence of Investigations	11
2.6 Alignment Survey	11
2.7 Geological Investigations	12
2.7.1 General	12
2.7.2 Purpose of Geological Survey	13
2.7.3 Sequence of Geological Investigations	14
2.7.4 Preliminary Studies	15
2.7.5 Site Investigations (Geological)	17
2.7.6 Detailed Exploration	18
2.7.7 Tests to be Conducted during Exploration	21
2.7.8 Shafts and Drifts	21
2.7.9 Preconstruction Investigations	22
2.7.10 Types of Rocks	22
2.8 Hydrological Investigations	22
2.9 Gases and Rock Temperatures	24
2.10 Rock Temperature	25

3	TRANSPORTATION TUNNEL REQUIREMENTS	27
3.0	Tunnel Requirements	27
3.1	Operational Requirements	27
3.1.1	Profile	27
3.1.2	Ruling Gradient	28
3.1.3	Curvature	28
3.1.4	Ventilation	28
3.1.5	Clearance	28
3.2	Structural Requirements	30
3.3	Construction and Maintenance	30
4	DESIGN OF TUNNELS	32
4.1	General	32
4.2	Alignment	32
4.3	Gradient	33
4.3.1	Examples	34
4.4	Curvature	34
4.5	Determination of Cross-section	36
4.5.1	Tunnel Clearance	36
4.6	Geometric Shape of Tunnel	38
4.6.1	Choices Available	38
4.6.2	Factors Affecting Choice	38
4.6.3	Selection of Shape	40
4.6.4	Influence of Tunnel Lining on a Cross-section	40
4.7	Design of Tunnel Lining	42
4.8	Rock Pressure	42
4.9	Theories Regarding Rock Pressure	43
4.10	Design of Tunnel Lining	48
4.11	Design Practice of Indian Railway Tunnels	50
	Annexure 4.1: Typical Analysis of a Box Section for Underground Metro Railway Calcutta	52
	Annexure 4.2: Design of Steel Support for Tunnel	65
5	SURVEY AND SETTING OUT	70
5.1	General	70
5.2	Survey Procedure	70
5.3	Setting Out on Surface	71
5.3.1	General	71
5.3.2	Progressive Ranging	71
5.3.3	Reciprocal Ranging	71

5.3.4	Traverse Method	73
5.3.5	Triangulation	74
5.3.6	Procedure for Angle Measurement	74
5.3.7	Required Degree of Accuracy in Triangulation	75
5.3.8	Use of Electronic Distance Measurements	76
5.4	Levelling	76
5.4.1	Benchmarks	77
5.5	Setting Out Inside Tunnels	77
5.5.1	Straight Alignment	77
5.6	Transferring Alignment Below G.L. at Intermediate Station	78
5.6.1	Tunnels Driven from Portals	81
5.6.2	Coplaning Method	81
5.6.3	The Weisbach Method	83
5.7	Setting Out Curves	85
5.8	Transition Curves	85
5.9	Work Line through Compressed Airlock	85
5.10	Case Study: D.B.K. Railline Tunnels	85
5.10.1	Railway Tunnel No. 36 on D.B.K. Rail Project	87
5.10.2	Triangulation	87
5.10.3	Laying Out Curves	87
6	TUNNELLING OPERATIONS	89
6.1	General	89
6.2	Definitions	91
6.3	Preliminary Work	91
6.4	Cut-and-Cover Tunnels	92
6.5	Tunnel Driving	92
6.6	Tunnelling Methods	93
6.7	Traditional Methods	93
6.7.1	Sequencing	94
6.7.2	Excavation and Advancing	94
6.8	Methods with Simple Tools	96
6.8.1	Forepoling Method	96
6.8.2	Tunnelling with Liner Plates	98
6.8.3	Needle Beam Method	98
6.8.4	Flying Arch Method	98
6.9	Shield Tunnelling	100
6.9.1	Shield	100
6.9.2	Accessories	102
6.9.3	Work Cycle	102
6.9.4	Special Precautions	103

6.10	Tunnelling in Rock	103
6.10.1	Methods	103
6.10.2	Codes Applicable	104
6.11	Tunnel Supports	104
6.11.1	Purpose of Tunnel Support	104
6.11.2	Types of Supports	105
6.11.3	Tolerances	108
7	DRILLING, BLASTING AND MUCKING	109
7.1	General	109
7.2	The Round	110
7.3	Drilling Pattern	110
7.4	Classification of Drill Holes	110
7.5	Depth of Holes	113
7.6	Diameter of Hole	113
7.7	Explosives	113
7.8	Drilling Operations	116
7.8.1	Drilling by wet method	116
7.8.2	Types of Drills	116
7.9	Safety	119
7.10	Mucking Procedure	122
7.10.1	General	122
7.10.2	Use of Rail Trucks	123
7.10.3	Loading	123
7.10.4	Cycle Time	124
7.10.5	Haulage	125
7.10.6	Mucking by Pumping	127
8	METRO TUNNELS	128
8.1	Introduction	128
8.2	Route Selection and Construction Methodology	128
8.2.1	Alignment	128
8.2.2	Utilities	129
8.2.3	Construction Methodology and Costs	129
8.3	Alignment and Track Design	130
8.4	Vertical Profile	131
8.5	Cover	132
8.6	Investigations	132
8.6.1	Geotechnical	132
8.6.2	Utilities	132
8.6.3	Road Traffic and Diversions	133
8.6.4	Building Survey	133

8.7	Method of Construction	134
8.8	Cut-and-Cover Construction	134
8.8.1	Method: Description and Types	134
8.8.2	H-Piles and Lagging or Sheet Piling	137
8.8.3	Diaphragm Walls	141
8.8.4	Bored Piles	141
8.9	Ground Movement Caused by Excavation	141
8.10	Tunnelling	144
8.10.1	Soft-ground Tunnelling	144
8.10.2	Shield Tunnelling	144
8.10.3	New Austrian Tunnelling Method	144
8.10.4	Tunnelling by Freezing	145
8.10.5	Tunnelling by Chemical Grouting	145
8.10.6	Tunnelling by Bentonite Slurry Shield	145
8.11	Slung Wall Construction	147
8.12	Construction Joints and Waterproofing	147
8.13	Design of Structure	150
8.14	Subaqueous Tunnels	150
9	LINING	153
9.1	Purpose of Lining	153
9.2	Timing Placement of Lining	154
9.3	Sequence of Lining	154
9.4	Formwork	155
9.4.1	Non-telescopic Formwork	155
9.4.2	Telescopic Formwork	156
9.5	Concreting	157
9.6	Compaction	160
9.7	Curing	160
10	VENTILATION, LIGHTING AND DRAINAGE	161
10.1	Ventilation	161
10.2	Vehicle Emissions	162
10.2.1	Exhaust Emissions	162
10.2.2	Carbon Monoxide	162
10.2.3	Carbon-Dioxide	163
10.2.4	Oxides of Nitrogen	163
10.2.5	Sulphur Dioxide	164
10.2.6	Hydrocarbons	164
10.2.7	Aldehydes	164
10.2.8	Particulates	164
10.3	Vehicle Emission Rates	164

- 10.4 Methods of Ventilation
 - 10.4.1 Types of Ventilation
 - 10.4.2 Longitudinal Ventilation
 - 10.4.3 Semi-Transverse Ventilation
 - 10.4.4 Full-Transverse Ventilation
- 10.5 Case Studies
 - 10.5.1 General
 - 10.5.2 Holland Tunnel
 - 10.5.3 Calcutta Metro Tunnel
- 10.6 Lighting
- 10.7 Drainage

REFERENCES

INDEX