



THE DESIGN AND CONSTRUCTION OF SHEET-PILED COFFERDAMS

B P Williams
D Waite



CONSTRUCTION INDUSTRY RESEARCH
AND INFORMATION ASSOCIATION
6 Storey's Gate
Westminster
London SW1P 3AU
Tel 071-222 8891
Fax 071-222 1708



THOMAS TELFORD PUBLICATIONS
Thomas Telford House,
1 Heron Quay
London E14 4JD
Tel: 071-987 6999
Fax: 071-538 4101

Contents

| | |
|--|-----------|
| List of Figures | 8 |
| List of Tables | 9 |
| Notation | 10 |
| 1 INTRODUCTION | 13 |
| 1.1 Cofferdams | 13 |
| 1.2 Temporary works | 14 |
| 1.3 Scope of the report | 14 |
| 1.4 Supervision of design and construction | 16 |
| 1.5 Causes of failure | 16 |
| 2 PROJECT PLANNING AND SITE INVESTIGATION | 17 |
| 2.1 Planning of the whole project | 17 |
| 2.2 The cofferdam in the context of the whole works | 17 |
| 2.3 Layout, clearances and access | 17 |
| 2.4 Movement of ground around the cofferdam | 17 |
| 2.5 Environmental considerations | 18 |
| 2.6 Site investigation | 18 |
| 2.7 Check list of information required from site investigation | 19 |
| 2.8 Planning for construction | 20 |
| 3 CONCEPTUAL DESIGN OF SHEET PILE COFFERDAM | 21 |
| 3.1 Appraisal of information | 21 |
| 3.2 Limitations on design | 22 |
| 3.2.1 Availability of plant and materials | 22 |
| 3.2.2 External supports | 23 |
| 3.2.3 Internal supports | 23 |
| 3.3 Ground pretreatment | 25 |
| 3.4 Choice of parameters for design and driveability | 26 |
| 4 DESIGN OF WALL | 27 |
| 4.1 Water and earth pressures on wall | 27 |
| 4.1.1 Total and effective stress | 27 |
| 4.1.2 Water pressures | 28 |
| 4.1.3 Earth pressures | 35 |
| 4.1.4 Earth pressure coefficients | 38 |
| 4.1.5 Choice of ground parameters | 38 |
| 4.1.6 Layered ground | 41 |
| 4.1.7 Sloping ground surface | 41 |
| 4.1.8 Check list for calculating active and passive pressures | 44 |
| 4.1.9 Variation of ground pressure due to wall flexibility | 44 |
| 4.1.10 Earthquake loads | 45 |
| 4.2 Other loads on cofferdam during construction and use | 45 |
| 4.2.1 Construction plant | 45 |
| 4.2.2 Spoil heaps | 45 |
| 4.2.3 Adjacent structures | 46 |
| 4.2.4 Other loads | 46 |
| 4.2.5 Lateral pressure on the wall due to loads other than uniform surcharge | 46 |
| 4.3 Analysis of wall | 47 |
| 4.3.1 Methods of analysis (cantilever or single prop walls) | 47 |
| 4.3.2 Strength factored | 48 |
| 4.3.3 Moments factored | 48 |
| 4.3.4 Choice of method of analysis | 51 |
| 4.3.5 Design for free or fixed earth support conditions | 51 |
| 4.3.6 Use of computers for design | 54 |

| | |
|--|-----------|
| 4.3.7 Multi-prop walls | 55 |
| 4.3.8 Soldier piles | 58 |
| 4.3.9 Design stresses in steel sheet piles | 59 |
| 4.4 Factors of safety | 60 |
| 4.4.1 Cantilever walls and propped walls with free earth support | 60 |
| 4.4.2 Propped walls with fixed earth support | 61 |
| 4.5 Overall stability | 61 |
| 4.5.1 Sloping sites | 61 |
| 4.5.2 Circular slip instability | 62 |
| 4.5.3 Bottom stability | 62 |
| 4.5.4 Pressure due to river or tidal flow | 64 |
| 4.5.5 Wave forces | 64 |
| 4.5.6 Overtopping | 65 |
| 4.5.7 Scour | 65 |
| 4.5.8 Protection from vessel impact | 65 |
| 4.6 Choice of pile section | 65 |
| 4.6.1 Section profile | 65 |
| 4.6.2 Choice of section to suit driving conditions | 66 |
| 4.7 General layout of sheet piling | 67 |
| 4.8 Check lists | 70 |
| 4.8.1 Design of cofferdam | 70 |
| 4.8.2 Check list for analysis of cantilever wall (simplified method) | 73 |
| 4.8.3 Check list for analysis of a propped wall with free earth support | 74 |
| 4.8.4 Check list for analysis of a propped wall with fixed earth support (simplified method) | 75 |
| 4.8.5 Check list for analysis of a multi-prop wall (using the stage-by-stage method) | 76 |
| 5 DESIGN OF SUPPORT SYSTEM | 78 |
| 5.1 General | 78 |
| 5.2 Walings | 78 |
| 5.2.1 Straight walings | 78 |
| 5.2.2 Circular walings | 82 |
| 5.3 Anchorages for external support | 84 |
| 5.3.1 Walings | 84 |
| 5.3.2 Anchors | 84 |
| 5.3.3 Passive anchors | 85 |
| 5.3.4 Ground anchors | 85 |
| 5.4 Struts for internal support | 86 |
| 5.5 Double-skin, earth-filled cofferdam | 89 |
| 6 CONSTRUCTION, MAINTENANCE AND REMOVAL OF THE COFFERDAM | 91 |
| 6.1 Control of work (including design) | 91 |
| 6.1.1 General | 91 |
| 6.1.2 Contractual requirements | 91 |
| 6.1.3 Statutory requirements | 91 |
| 6.1.4 Other legal liabilities | 92 |
| 6.1.5 Organisation of temporary works control | 92 |
| 6.1.6 Responsibilities of the temporary works coordinator | 93 |
| 6.2 Installation of sheet piles | 93 |
| 6.2.1 Types of pile driving equipment | 93 |
| 6.2.2 On site storage of piles | 94 |
| 6.2.3 Pitching and driving | 96 |
| 6.2.4 Order of driving | 100 |
| 6.2.5 Safety | 101 |
| 6.3 Excavation | 101 |
| 6.4 Sealing of leaks and separated interlocks (or isolated piles not driven to level) | 103 |
| 6.5 Control of water | 103 |
| 6.6 Access and safety | 104 |
| 6.7 Maintenance of the cofferdam | 104 |

| | |
|--|-----|
| 6.8 Monitoring of the cofferdam | 105 |
| 6.9 Removal of the cofferdam | 105 |
| References | 107 |
| Bibliography | 111 |
| 1.0 GENERAL COVERAGE AND REFERENCE | 111 |
| 2.0 HISTORICAL | 111 |
| 3.0 DESIGN, EARTH AND WATER PRESSURES | 112 |
| 4.0 CONSTRUCTION | 115 |
| Appendix A Soil and water pressures on retaining wall | 116 |
| General principles | 116 |
| Earth pressures on the wall | 118 |
| Granular soils | 118 |
| Cohesive soils | 119 |
| Appendix B Worked design examples | 121 |
| Example No 1: Design of sheet pile wall for a cofferdam | 121 |
| Example No 2: Design of internal frame for a cofferdam | 158 |
| Example No 3: Use of flow net diagram | 170 |
| Example No 4: Earth pressures for layered ground with non-uniform slopes | 185 |
| Appendix C Safety regulations | 188 |
| Appendix D Dimensions and properties of steel sheet piles manufactured in the United Kingdom | 196 |