DEVELOPMENTS IN GEOTECHNICAL ENGINEERING 34B

PRACTICAL PROBLEMS IN SOIL MECHANICS AND FOUNDATION ENGINEERING, 2

WALL AND FOUNDATION CALCULATIONS, SLOPE STABILITY

GUY SANGLERAT
GILBERT OLIVARI
BERNARD CAMBOU

Translated by G. GENDARME

ELSEVIER
Amsterdam – Oxford – New York – Tokyo 1985

UNIVERSITA' DEGLI STUDI DI TRENTO
BIBLIOTECA

CONTENTS

Introduction V
Notations IX
Engineering Units XIII

Chapter 7. Retaining Walls
7.1 Earth pressures on a vertical wall, horizontal backfill, above the water table . . 1
7.2 Earth pressure considering the water table on a vertical wall 3
7.3 Retaining wall with horizontal backfill; overturning stability and sliding stability 5
7.4 Wall stability without a buttress and with an inclined backfill 13
7.5 Comparison of lateral forces on a vertical wall with horizontal backfill and different assumptions (Boussinesq equilibrium and graphical method of Culmann) 15
7.6 Detecting errors made in the design of failing retaining structures (ruptures, collapses, etc.) of reinforced concrete or masonry 16
7.7 Diagram of stresses behind a gravity wall. Stratified soil and water table. Uniformly loaded backfill 18
7.8 The influence of drainage conditions on the earth pressures acting on a retaining wall 19
7.9 Analysis of the failure of a reinforced concrete retaining-wall. Corrective measure by using rock anchors 24
7.10 Design of a reinforced-earth retaining-wall with horizontal backfill 30
7.11 Design of a reinforced earth retaining-wall with a reinforced concrete skin and a slope, surcharged backfill 37

Chapter 8. Sheetpile Walls
8.1 Design of a sheetpile wall. Comparison of two design methods: the classical method of plasticity, and the design by elasto-plasticity 43
8.2 Design of an anchor system 53
8.3 Design of a sheetpile wall with anchors by the Blum method 58
8.4 Design of an anchored sheetpile wall by the method of Tschebotarioff 63
8.5 Design of fender piles 66
8.6 Uplift of an excavation bottom 92

Chapter 9. Slurry Walls
9.1 Slurry wall stability during construction 103
9.2 Design of a slurry wall with pre-stressed anchors 105
9.3 Self-sustaining slurry wall 114
9.4 Wall buttressed by floors 118

Chapter 10. Shallow Footings
10.1 Allowable bearing capacity of a strip footing on sand 123
10.2 Evaluation of the bearing capacity factor N_γ 123
10.3 Bearing capacity of a strip footing embedded in sand 125
10.4 Bearing capacity of a strip footing embedded in a cohesive soil 125

10.5 Bearing capacity of a square footing on a cohesionless or cohesive soil 126
10.6 Comparison of footings and mat foundation 126
10.7 Comparison of settlements of a footing and of a mat supporting a building over a two-layer system 131
10.8 Settlement of a mat on a two-layered system 134
10.9 Elastic and plastic equilibrium in a soil under a strip footing 135
10.10 Design of a shallow footing based on laboratory test results 147
10.11 Shallow footings on a two-layer system 151
10.12 Circular mat design for the support of a stack (shallow footing with an eccentric, inclined load by the method of Tran Vo Nhiem) 153
10.13 Design of footings on swelling clay. Evaluation of swelling pressures and computations of possible differential uplifts 155
10.14 Evaluation of the bearing capacity and settlement of a shallow footing on a cohesive soil from results of a pressuremeter test 164
10.15 Evaluation of bearing capacity and settlement of a shallow footing on a cohesionless soil from results of a pressuremeter test 166
10.16 Bearing capacity and settlement calculations of a mat foundation on a two-layered system from pressuremeter test results 169
10.17 Bearing capacity of shallow foundations from static penetrometer tests 172

Chapter 11. **Deep Foundations**
11.1 Design of a driven pile in homogeneous sand from static penetrometer test data 173
11.2 Design of a pile driven in a heterogeneous soil from static penetrometer test data 174
11.3 Design of drilled piles from static penetrometer test data (Andina penetrometer) 176
11.4 Design of a pile driven into a three soil layer system from static penetrometer test data 179
11.5 Design of a driven pile on the basis of static formulae 179
11.6 Allowable bearing capacity of a pile from pressuremeter test results 184
11.7 Design of a pile and pier drilled into a swelling clay 187
11.8 Enlarged base pile design in a swelling clay 190
11.9 Calculation of the bearing capacity of a pile from the S.P.T. (Standard Penetration Test) 194
11.10 Bearing capacity of a driven pile from static-penetration dynamic-penetration tests and S.P.T. Comparison with in situ pile load test 194
11.11 Determination of bearing capacity and settlements estimates of semi-deep foundations based on pressuremeter tests 202

Chapter 12. **Slopes and Dams**
12.1 Failure of a vertical cut 207
12.2 Plane failure 210
12.3 Dam stability (global method) 212
12.4 Dam stability (method of slices) 219
12.5 Stability of a dam with impervious core. Comparison of results from computer calculation and slice method 221
12.6 Design of a retaining-wall on unstable slope 226
12.7 Embankment stability on a compressible soil 238

Bibliography 245

Index 249